PERSONAL DIGITAL ASSISTANTS AS A MOBILE INSPECTION SYSTEM AT CONSTRUCTION SITE

A. Abdullah, O.B. Thai

Department of Structures & Materials, Civil Engineering Faculty, Universiti Teknologi Malaysia, 81310 UTM Skudai, Malaysia E-mail: <u>arham@utm.my</u>

ABSTRACT: Construction defects are always the key concern of the construction industry. Different constructed facilities generate different types of defects and demanded different levels and types of quality, depending on the functions, system types, and materials used. Nevertheless, construction projects was typically take place in an environment where it is difficult to gain access to conventional computers for use as realtime decision aids as the gone through the project quality inspection. The objectives of this study were to identify the inspection process and standard check list used in practice at construction site; to identify the potential and requirement for mobile inspection system at construction site and to develop a prototype of a mobile inspection system for construction site. Data was gathered from the literature study and also through local construction organizations by means of interviews and questionnaires. A prototype was developed using rapid prototyping method in a final phase. The finding revealed that in general construction industry does not have its standard inspection process and standard check list in practice. Besides this, the study also reveals that there was a potential and needs for mobile inspection system at construction site. Finally a mobile defect inspection which consists of a sub system checklist and reference system was developed to suit the need of industry. The developed prototype will standardize the way of managing defects and improve quality, increased productivity of inspectors, and accurate photographic records.

Keywords: Mobile inspection system, construction site, construction defects

1.0 INTRODUCTION

Construction defects are always the key concern of the construction industry. Different constructed facilities generate different types of defects and demanded different levels and types of quality, depending on the functions, system types, and materials used. Most research on defect concentrates on materials and systems, examining different types of defects under given conditions and determining methods for how to detect them. As a result, these researches are generally focused on technical and technological issues. Numerous systems have been designed to eliminate defects during construction operations. Many of these systems were very effective in detecting and eliminating defects that occurred at the construction stage, but a large number of complaints about defects were also recorded a few years after the occupants moved in, which suggested that there were still loopholes in the existing inspection and management systems (Chong and Low, 2005).

Construction projects typically take place in an environment where it is difficult for site engineers or project engineers at construction site to gain access to conventional computers for use as real-time decision aids as they gone through the project evaluation, building mechanical & electrical inspection, or the pre and post concrete quality inspection (Williams, 2003). Therefore there is a need to develop a functional prototype of Mobile Defect Inspection System (MDIS) which will help site engineers to carry out a defect inspection process by maintaining a good record keeping, minimizing office work and enhance the communication between construction site and site office.

2.0 POTENTIAL OF HANDHELD PC IN CONSTRUCTION INDUSTRY

Traditionally, the construction industry has employed paper-based data capture and communication methods. These were time-consuming and potentially error-prone, and discouraged project managers from using them on a regular basis. Thus people tend to minimize communication with other project participants. Since the various stages and tasks of construction are highly interdependent this minimal interaction in practice causes severe problems, widely reflecting on other partners and the final construction product (Ladh, 1995). It has been recognized for some time that capturing data through handheld computing devices, enabled with suitable wireless capability, can address these problems, thereby increasing operative efficiency and ensuring better integration with the existing project management systems.

Therefore, reference information is one of the basic uses for which handheld computers can be employed. The specific information included on the handheld device will vary from project-to-project and organization-to-organization. It would be assumed that contractors would place more of an emphasis on installation procedures, and owner organizations would emphasize documentation for inspection procedures and quality control. Typical documentation that can be accommodated on a handheld computer is such as real time progress monitoring of on-site works, remote expert support, on-site collection of qualitative and quantitative measurements, collaborative review of technical drawings, on-site supplier and subcontractor evaluation, on-site evaluation of equipment usage measurements, keeping track of the physical equipment position anytime and anywhere, answering audit checklists and filing audit reports during site audits (Meissner et.al. 2001).

The rapid growth of handheld computing devices in recent years has marked the beginning of a real mobile communication capability. From their roots as standalone devices that were reliant upon a cable connection to a desktop PC or a connected mobile phone, handhelds are now evolving to integrate features that enable wireless connection to mobile phone and corporate networks. However to a large extent, current use of mobile communication devices for the construction industry remains limited to use of standalone hand held device (Anumba et.al, 2002).

Nevertheless the used of PDA¹ and telecommunications are long exits in Construction industry and there are few research been carries out on concept of using obsolesce technology such as concept of using Psion as mobile web browser to browse through the internet at any ware in the paper of "PDA as mobile WWW browsers" (Gessler, 1995), and also using handheld computer to browse through an electronic document such as e-book in the construction industry and also using a third party software for data collection in the paper of "Applying Handheld computers in the construction industry" (Williams, 2003).

Later, the player in the construction industry had aware of the need of more capable mobile computing system in the construction industry due to the booming of information technology, then they had put their mind into and develop a concept of interaction between mobile computing system and construction in the paper "Mobile Communication In Construction-Trends And Prospects" (Anumba et.al, 2002)". In the paper of "The application of PDA as mobile computing system on construction management" (Kimoto et.al, 2005) had draft out a stand along construction management prototype where the information collection from construction site is not transmit instantaneous and only can be retrieve and analysis when the mobile device is send back to office, further more the interface use in this prototype is a set of static programs which more to structure engineering analysis. Therefore it can not perform dynamic interaction to collect data due to the dynamic nature of construction environment.

¹ According to Apple Computer Inc (The Founder), the terminology of PDA is define as personal digital assistants which is a tools that would hold telephone numbers, keep your calendar, store notes, plus send and receive data wirelessly.

3.0 PROTOTYPE DEVELOPMENT

To serve the purpose of mobile defect inspection system, basically the MDIS is design to support two separate system parts. One part is a moveable part such as Pocket PC which runs with window CE system, and the other part is to serve a workstation which is moveable in the office for administration purpose such as Microsoft Windows 98 OS and above. The mobile support part in MDIS is design to let user to enter the data and information at any place and any time. This mean the user do not have to go back to the office to renter the data into the work station, because all the data and information was stored in the internet portal server. Therefore, the user of the MDIS can retrieve and store information where ever they go and where ever the site is located, provided as long as there is a cellular network signal and can be connected to internet. However on the other hand, the MDIS also designs to include the non moveable unit such as work station in the office. This is to serve the purpose of defect report reference system to contractor who involve in the project and also to serve the purpose of system admin in database and also MDIS core system maintenance (Figure 1).




Figure 1: MDIS system topology

3.1 Database System Design

Similar to other study approach, to create a proper work flow of defect management process is to collect and study their defect process and then reengineered it to more effective and smooth defect management process as in Figure 2. Then by conducting Data Flow Diagram study, the source of input and the source of output to the MDIS system can be identified (Figure 3).




Figure 2: Defect Management Business Process




Figure 3: Data Flow for Input and Output from MDIS

Later, with the combine of reviewed and an adoption of standard defect check list from the study of "Penyediaan Senarai Semak Untuk Pemeriksaan Di Tapak Bina Bagi Kegunaan Jabatan Kerja Raya Penampang Sabah" (Nelliah, 2005), the blue print of the complete database for the MDIS was developed as in Figure 4. The basic concept of the MDIS database structure was based on seven key elements which were:-

i. List Of Standard Defect Check List

A standard defect check list proposed by previous researcher (Nelliah, 2005) which consists of 10 types most commonly used defect check list by the local Malaysian construction industry.

ii. Inspection Information

Contain necessary information to access current inspection such as inspection type, type of buildings, project name and block name.

iii. Employee Information

Consists of basic information of all employees involve in the project team and includes the inspector's background information.

iv. Level

Information which is use for accessing multistory building.

v. Location

Hold information of section in a building, example: Car park, Master Bedroom and Kitchen.

vi. Contractor Information

All the necessary basic background information of contractor will be stored. Example: Contractor's trade.

vii. PTD Number

PTD number was a very unique lot number which is register and assign by the land office of Malaysia to a particular lot of land or property, therefore this section will hole the information of the PTD number which will be use as a unique primary key to store defect information.

Microsoft Access was chosen as primary software used to manage and create the MDIS database in earlier stage. In the implementation stage of MDIS in the web portal, Active Server Language was used to access the server in retrieving and updating the MDIS portal database.




Figure 4: MDIS database

3.2 System Architectural Design

The system architecture of MDIS basically was supported by 9 functional modules written in Active Server Page Language. Each module function is unique and interacted with each other so that it serve the function of database management and control; OS detection and GUI control; image processing; information access security control by level and group; data export; data print; report auto generation; database acquisition; and data post (Figure 5).




Figure 5: MDIS main system architectural

3.3 System Platform

As mentioned earlier, the MDIS system is design to support across two different OS platform which is Win CE and Standard Microsoft Windows 98 and above, therefore it is important to select a language which can communicate between these two different OS platform. Besides this, never to forget that the MDIS is an application which need to be designed and operated in a Internet Information Service (IIS) server to retrieve and save information inside the server database (Figure 6).

Therefore, in this MDIS project, Active Server Page Language (ASP), Visual Basic (VB) Language and JAVA was used as a medium which communicate through three different platforms. First, the ASP language was used as the primary medium to interact most of the process server instruction between these three different platforms. Second, the VB language was used in some form design and security checksum, and finally, the JAVA language was used in the table form to control the Graphics User Interface (GUI). Although the JAVA language was used to control tables form GUI, but the orientation and presentation of information to the user at different platform was controlled by the Hyper Text Markup Language (HTML).

For the information database retrieval at portal server, it was controlled by the ActiveX Data Object (ADO) method in order to connect the user to the database. After it have been connected to the database, it is more appropriate to use Structured Query Language (SQL) to retrieve the data or the information in the way as the end user required.




Figure 6: Cross platform function

4.0 Conclusions

By comparing the construction scenario in 80's and today, the role of information technology in construction industry have become more important because most of the construction process is going for automation and simplification. Therefore it is very important for the construction company to equip themselves with appropriate IT tools and technology in order to survive in a very competitive industry.

The development of a functional Mobile Defect Inspection System (MDIS) (Figure 7) is tailored with the current construction industry scenario which emphasized more on mobile computing at construction site. Hopefully the prototype will help site engineers to carry out a defect inspection process in a more efficient way by incorporating several advantages as follows:

- a. Standardize the way of managing defects and improve quality (Figure 8).
- b. Accurate photographic records and improved communication to contractors (Figure 9).
- c. Increased productivity of inspectors by eliminating the need for data entry back in the office and centralize and standard defect management platform (Figure 10)
- d. Eliminate delays in communicating defects to contractors (Figure 11).
- e. Instant Auto Generations for Defect Report (Figure 12)

MetFront v3.1 [http://169.254.18	√ { 11:52)2.182/try9/si ▼ 💓		I.	MetFront v3.1 4< 11:50	
Back to list		-		HA	
PTD	127 👻			No. of Concession, Name	
INSPECTION	1 -	=		Checking Template	=
LOCATION	BEDROOM 1 👻			TYPE OF FORM	
LEVEL	2 🔻			site_preparation	Ē
Contractor	B SDN BHD 👻			site_clerance concrete	
Rubbish Clearance				services	
Site Clearance	₩	•		built_in_fitment	
4	•			reinforcement_bar	
File ¥iew Tools 🖉	. ≥ 6 <mark>Z ⊂ E</mark> ∠			File View Tools 🛆 💩 💆 🖼 🖺	<u>_</u>
					-

Figure 7: A Mobile Inspection Prototype

Figure 8: A Standard Inspection Checklist

) 🥂	NetFront v3.1	4 € 12:02	8
htt	p://169.254.182.18	32/try9/si 🔻 📢	6
	water leakage	*	<u> -</u>
	and -	1	=
	The second second		-
ABO	abc	■ 123	
		+	
			」spc ↓ @b
File	View Tools 🙇 🗻		

Figure 9: Photographic Records in Prototype

REENT DEFECT STATUS ARE BASE ON THE LAST UPDATE TO SEVER ADMINISTRATION Y DATE IS : 3/21/2006 And THE TIME IS : 6:26:02 AM MENU LOGGING FROM : 127.0.0.1 MENU OF DEFECT REMAIN IN SITE PREPARATION AND 0 OF THE DEFECT IS COMPLETED			OF THE DEFECT IS COMPLETED	02 AM	AY DATE IS : 3/21/2006 And THE TIME IS : 6:26 RENT LOGGING FROM : 127.0.0.1
OP DEFECT REMAIN IN SITE CLEARANCE AND 1 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN ELECTRICAL WORKS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN FEMORY REVEAT BAR AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN FEMORY REVEATING AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF TOTAL DEFECT LOGGED IN 0 OF THE DEFECT IS COMPLETED OF TOTAL DEFECT LOGGED IN 0 OF THE DEFECT IS COMPLETED	d Transme	PACIENT OF CHILL MANAGEMENT	OF THE DEFECT IS COMPLETED		OF DEFECT REMAIN IN SITE PREPARATION AND
OP DEFECT REMAIN IN SITE CLEARANCE AND 1 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN ELECTRICAL WORKS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN FEMORY REVEAT BAR AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN FEMORY REVEATING AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PERFORMERS AND 0 OF THE DEFECT IS COMPLETED OF TOTAL DEFECT LOGGED IN 0 OF THE DEFECT IS COMPLETED OF TOTAL DEFECT LOGGED IN 0 OF THE DEFECT IS COMPLETED	Trace inc	FROMEW OF COVER SOUTHERE	OF THE DEFECT IS COMPLETED		
OP DEFECT REMAIN IN SCONCRETE AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN BULK IN TIMENT AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN RELECTRICAL WORKS AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN RELECTRICAL WORKS AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN PREVORKS AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN PREVORKS AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN PROVINCIAL AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN PROVINCIAL AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN PROVINCIAL AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN PROVINCIAL AND 0 OF THE DEFECT IS COMPLETED OP DEFECT REMAIN IN PROVINCIAL AND 0 OF THE DEFECT IS COMPLETED OP TOTAL DEFECT COMPLETED 0 OF THE DEFECT IS COMPLETED OF TOTAL DEFECT COMPLETED 0 OF THE DEFECT COMPLETED OF TOTAL DEFECT COMPLETED 0 OF THE DEFECT COMPLETED OF TOTAL DEFECT COMPLETED 0 OF THE DEFECT COMPLETED O	O'PIELER THE	PACIENT OF COVER TONTHERATOR			OF DEFECT REMAIN IN SITE CLEARANCE AND
SP DEFECT REMAIN IN SERVICES AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN ENERVICES AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN ENERVICES AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN ENERVICES AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN ENERVICES AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN ENERVICES AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN ENERVICES AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN FORMAVORICS AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN FORMAVORICS AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN FORMAVORICS AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN FORMAVORICS AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN FORMAVORICS AND 0 OF THE DEFECT IS COMPLETED SP DEFECT REMAIN IN FORMAVORICS AND 0 OF THE DEFECT IS COMPLETED SP DEFECT CONDUCTION NSPECTION INFO BLOCK INAME SP TOTAL DEFECT LOGGED IN NSPECTION TYPE LEVEL LOCATION SP OF BULLDING TYPE OF FOLDING SP TOTAL DEFECT SCOMPLETED					
OP DEFECT REMAIN IN REMPORCEMENT BAR AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN REMPORCEMENT BAR AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN INSENSING AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN INSENSING AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN INSENSING AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PRE-WORKS AND 0 OF THE DEFECT IS COMPLETED DEFECT REMAIN IN PRE-WORKS AND 0 OF THE DEFECT IS COMPLETED DEFECT REMAIN IN PRE-WORKS AND 0 OF THE DEFECT IS COMPLETED DEFECT REMAIN IN PRE-WORKS AND 0 OF THE DEFECT IS COMPLETED DEFECT REMAIN IN PRE-WORKS AND 0 OF THE DEFECT IS COMPLETED DEFECT REMAIN IN PRE-WORKS AND 0 OF THE DEFECT IS COMPLETED DEFECT LOGGED IN 0 OF THE DEFECT IS COMPLETED NESECTION TYPE DEFECT COMPLETED 0 OF THE DEFECT COMPLETED NESECTION TYPE DEFECT COMPLETED 0 OF THE DEFECT COMPLETED TYPE OF BUILDING DF TOTAL DEFECT COMPLETED 0 OF THE DEFECT COMPLETED TYPE OF DILDING DF TOTAL DEFECT COMPLETED 0 <t< td=""><td></td><td></td><td>OF THE DEFECT IS COMPLETED</td><td>0</td><td>OF DEFECT REMAIN IN SERVICES AND</td></t<>			OF THE DEFECT IS COMPLETED	0	OF DEFECT REMAIN IN SERVICES AND
OP DEFECT REMAIN IN FREIZENTICAL WORKS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN FREIXENS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PROVINCES AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PROVINCES AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PROVINCES AND 0 OF THE DEFECT IS COMPLETED PROJECT CONDITION 0 OF THE DEFECT IS COMPLETED DEPECT REMAIN IN PROVINCES AND 0 OF THE DEFECT IS COMPLETED DEPECT REMAIN IN PROVINCES AND 0 OF THE DEFECT IS COMPLETED DEPECT REMAIN IN PROVINCES AND 0 OF THE DEFECT IS COMPLETED DEPECT LOGGED IN OF TOTAL DEFECT COMPLETED INSPECTION INFO DE OF TOTAL DEFECT COMPLETED INSPECTION INFO DE OF TOTAL DEFECT COMPLETED INSPECTION INFO Status INSPECTION INFO Level INCARTOR Status INTERNAL MENCORE ON TOTAL DEFECT LOGGED IN OF TOTAL DEFECT COMPLETED Status INTERNAL EMPLOYEE CONTRACTOR IST OF TOLIST DEFECT POLIST INTERNAL DEFECT POLIST PTOLIST			OF THE DEFECT IS COMPLETED	0	OF DEFECT REMAIN IN BUILT IN FITMENT AND
OF DEFECT REMAIN IN PRISHING AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN PREWORKS AND 0 OF THE DEFECT IS COMPLETED PROJECT NAME 0 OF THE DEFECT IS COMPLETED PROJECT CONDITION 0 OF THE DEFECT IS COMPLETED PT TOTAL DEFECT LOGGED IN 00 TOTAL DEFECT CONDITION DIA NOT SUMMIT THE PICTURE OVER Size 640 pixel X 480 pixel in to the server INTERNAL BMPLOYEE INTERNAL BMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM			OF THE DEFECT IS COMPLETED	0	OF DEFECT REMAIN IN REINFORCEMENT BAR AND
OP DEFECT REMAIN IN PPE WORKS AND 0 OF THE DEFECT IS COMPLETED OF DEFECT REMAIN IN FORMWORKS AND 0 OF THE DEFECT IS COMPLETED ER ALL PROJECT CONDITION 0 OF THE DEFECT IS COMPLETED DP TOTAL DEFECT LOOGED IN OF TOTAL DEFECT COMPLETED NSPECTION INFO DF TOTAL DEFECT LOOGED IN OF TOTAL DEFECT COMPLETED NSPECTION INFO DF TOTAL DEFECT COMPLETED NSPECTION INFO			OF THE DEFECT IS COMPLETED	0	OF DEFECT REMAIN IN ELECTRICAL WORKS AND
OF DEFECT REMAIN IN PROVINCES AND 0 OF THE DEFECT IS COMPLETED PP DEFECT REMAIN IN PORTMACRICS AND 0 OF THE DEFECT IS COMPLETED ER ALL PROJECT CONDITION NSPECTION INFO DY TOTAL DEFECT LOGGED IN 97 TOTAL DEFECT COMPLETED NSPECTION TYPE LOCATION TYPE OF BUILDING Of thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL BMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM			OF THE DEFECT IS COMPLETED	0	OF DEFECT REMAIN IN FINISHING AND
OP DEFECT REMAIN IN FORMAVORIES AND [0] OF THE DEFECT IS COMPLETED ER ALL PROJECT CONDITION BLOCK NAME DP TOTAL DEFECT LOGGED IN OF TOTAL DEFECT COMPLETED NSPECTION INFO DF TOTAL DEFECT COMPLETED CONTACTION Of thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL EMPLOYEE CONTACTOR UST PTD LIST TYPE OF FORM TYPE OF FORM			OF THE DEFECT IS COMPLETED	0	OF DEFECT REMAIN IN PIPE WORKS AND
ER ALL PROJECT CONDITION DF TOTAL DEFECT LOGGED IN OF TOTAL DEFECT COMPLETED of thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL BMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM			OF THE DEFECT IS COMPLETED	0	OF DEFECT REMAIN IN FORMWORKS AND
INSPECTION TYPE LEVEL LOCATION TYPE OF BUILDING of thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL BMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM	and the second se	and the second sec			
ER ALL PROJECT CONDITION LEVEL DOCATION TYPE OF BUILDING DF TOTAL DEFECT COMPLETED TYPE OF BUILDING Soft thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL EMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM					
DF TOTAL DEFECT LOGGED IN DF TOTAL DEFECT COMPLETED : of thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL EMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM	(YPE			ION	ED ALL DROJECT CONDIT
DF TOTAL DEFECT LOOGED IN DF TOTAL DEFECT COMPLETED of thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL BMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM		the second s			ER ALL PROJECT CONDIT
of TOTAL DEFECT COMPLETED of thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL EMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM			_		
of thumb, do not summit the picture over size 640 pixel X 480 pixel in to the server INTERNAL BMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM	.DING	TYPE OF BUILDING			
INTERNAL EMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM			190 minut in the star summer	10 minut 37 4	
EMPLOYEE CONTRACTOR LIST PTD LIST TYPE OF FORM			400 pixel ili to ule server	to pixel A 4	or mumo, do not summit the picture over size o
CONTRACTOR LIST PTD LIST TYPE OF FORM	AL	INTERNAL			
TYPE OF FORM	Æ	EMPLOYEE			
TYPE OF FORM	LIST	CONTRACTOR LIST			
		PTD LIST			
	DPM	TYPE OF FORM			
SITE PREPARATIONS					
SITE CLEARANCE					

Figure 10: Centralize and Standard Defect Management

New Page 1 - Micr	osoft Internet Explo	rer				T (7) 🛛
File Edit View Fav	orites Tools Help					Ar
🔇 Back 🔹 🔘 🕤	🗷 🗟 🏠 🔎	Search ☆ Favorites 🌘	🕈 Media 🤣 🍰 -	🎍 🛛 - 🛄 💽		
Address 🙋 http://localh	ost/TRY11/guessmenu.asp	2				💌 🛃 Go 🛛 Links 🌺
WELLCOM	E TO					UTM.MY
	E TU IS TEST SII					07794,1977
UTM THES	ia rear an	E				
Logged as A SDN BHD	group 0 Log out					
	88.88 00000000					
		ALLA TEL		TTY ANT		
DUTUCT AND				-inflation and		
DEFECT AND	KEPAIK		-	Carps.		
		FFF		Charles of Charles		
				and the second se		
CURRENT D	EFECT STAT	US ARE BASE	DN THE LAST	UPDATE TO SE	IVER	
TODAY DATE IS : 3/1/20	IO6 And THE TIME IS : "	11:50:13 AM				
CURRENT LOGGING FRO						
		SITE PREPARATION A	TIVITY (Drint)			
CONTRACTOR	PTD	INSPECTION	LOCATION	LEVEL	COMMENT	STATUS
A SDN BHD	111	2	BEDROOM 2	23		INCOMPLETE
	11.5556	1.5	T HERE SOLVE AND HOL	1.55		1
DEFECT TO YOU A		OTTO OLE ADAMON ANT	B UT Car i va			
		SITE CLEARANCE ACT				
CONTRACTOR	PTD	INSPECTION	LOCATION	LEVEL	COMMENT	STATUS
A SDN BHD	114	3	BEDROOM 1	26		INCOMPLETE
DEFECT TO YOU AT	TTENTION UNDER IN	CONCRETE ACTIVITY (F	Print]			
CONTRACTOR	PTD	INSPECTION	LOCATION	LEVEL	COMMENT	STATUS
Done	- 17 				1	Second Intranet
	🥭 💼 🦈 ն My Do	aumanta Alta	Dana (Minana			🔹 🌮 11:50 AM
🐮 start 🔰 🛍		icuments 🧧 🙆 Ne	ew Page 1 - Microso			11:50 AM

Figure 11: Better Defect Communication with Contractor

G · O · 🖡	3 🕼 🔎 📩 🏵	🔗 🎍 🔯	•
MDIS	DEFECT FORM	REFERENCE	: MDIS-
muns	DEFECT FORM	INSPECTION	: 3
		DATE	: 3/21/2006
ARCHITECIU	ARCHITECTURAL & BUILDING WORKS STATUS		: INCOMPLETE
CONTRACTOR	: Haji Ismail Bin Ishak		
UNIT	LOCATION		LEVEL
114	BEDROOM 1		26
	Π		J
	ITEM		CONDITION
Rubbish clerance			**INCOMPLETE
Demolition of wor	ker's accommodation		COMPLETED
Construction equip	pment		COMPLETED
Demolition of temp	porary toilet		COMPLETED
Site office			COMPLETED
Disconnected of th	he services supply		COMPLETED
	PICTURE	CO	MMENT
		roof ful with rubbisl	n

Figure 12: Instant Auto Generations for Defect Report

5.0 REFERENCES

- Anumba C.J, Aziz A and Obonyo E.A, (2002), "**Mobile Communications in Construction Trends and Prospects**", Department of Civil and Building Engineering, Loughborough University, UK.
- Chong W. K, and Low S.P, (2005), "Assessment of Defects at Construction and Occupancy Stages", Journal of Performance of Constructed Facilities November 2005, ASCE, pg 283-289.
- Gessler S, (1995), "PDA As Mobile WWW Browsers"
- Kimoto K, Endo K, Iwashita S and Fujiwara M, (2005), "The Application of PDA as Mobile Computing System on Construction Management", Automation in Construction Vol. 14, 2005, Elsevier, pg 500-511.
- Ladh, (1995), "**Reorganising the building process**", VTT Publications 258, Technical Research Centre of Finland, Espoo, Finland.
- Meissner, A., Baxevanaki, L., Mathes, I., Branki, C., Bozios, T., Schonfeld, W, Crowe, M., Steinmetz, R (2001). "Integrated Mobile Operations Support for the Construction Industry: The COSMOS Solution", The 5TH World Multi-Conference on Systemics, Cybernetics and Informatics, SCI 2001, Int. Institute of Informatics and Systemics, July 2001, Orlando, USA: pp. IV/248-255
- Nelliah S, (2005), "**Penyediaan Senarai Semak untuk Pemeriksaan di Tapak Bina bagi Kegunaan Jabatan Kerja Raya Penampang, Sabah**", Universiti Teknologi Malaysia : Tesis Sarjana Muda.
- Williams T. P (2003), "Applying Handheld Computers in the Construction Industry" Practical Periodical on Structural Design and Construction Vol. Nov, 2003 ASCE, pg 226-229