

**CONSTRUCTION OF PRECAST SEGMENTAL BOX GIRDER BRIDGE  
USING OVERHEAD GANTRY  
– A CASE STUDY**

**JAZLAN BIN SALLEH @ MOHAMED SALLEH**

A project report submitted in partial fulfillment of the  
requirements for the award of the degree of  
Master of Science (Construction Management)

**Faculty of Civil Engineering  
Universiti Teknologi Malaysia**

**NOVEMBER 2006**

To my beloved wife, Siti Shairra Zakaria, my children Nurul Asyikin, Mohd Amir Arif, Nurul Amira, Mohd Amir Afiq.....  
.....thank you for your love, support and patience during this hard time.

I love you so much!!  
7november2006

## ACKNOWLEDGEMENT

I would like to express my sincere appreciation and thousands of thank you to my project supervisor, Professor Madya Dr. Mohamad Ibrahim Mohammad for being patience with me, for his encouragement, guidance, critics, advice and motivation and last not least the valuable friendship.

While preparing this project, I was in contact with many people, academicians, and construction professionals in construction firm, consultants and suppliers. They have contributed towards my understanding and thoughts. In particular, I am also very thankful to all of them for their willingness to share their valuable knowledge, expertise and technical know-how which assist me a lot in preparing this project. Without their continued support and interest, this project would not have been the same as presented here.

I am also would like to thank all the lecturers who have conducted the course from the beginning and not hesitating to share their knowledge with us. I am grateful to all my family members who are very understanding and have been patience with me during my hard time. My fellow postgraduate students should also be recognized for their support. My sincere appreciation also extends to all my colleagues and others who have provided assistance at various occasions. Their views and tips are useful indeed. Unfortunately, it is not possible to list all of them in this limited space.

## ABSTRACT

The bridge construction utilizing the concept of erecting the precast segmental panel has been a chosen method for bridge construction within restricted area. This method has been successfully exhibit the constructability within the urban area and also crossing the wide water body, valley and existing highway or railroad. The suitability of this method of construction is depending on the availability of working space, which govern the major cause in selection of this construction method. The aim and objective are to study the problem in the manufacturing the segment and segment erection. This master project has studied the procedures in construction of precast segmental box girder bridge by balance cantilever method using the overhead gantry. This project also studied the segment manufacturing procedures and discovers some problem problems faced in segment manufacturing that is interesting and need to expose for awareness to the bridge professional. The segment erection procedures and sequence also has been studied and the related problems have been highlighted and need further study by the professional bridge designers and constructors. The study has been conducted by direct structured interview and questionnaire with the bridge expertise. The bridge professional from consultants, segment manufacturer, main contractors and specialist sub contractor have shared their knowledge, technical know-how and experience and has been elaborated in details in this project. The finding is very interesting and it has exposed the problem related to the segmental bridge construction that need further study by the bridge expertise. This study also recommended some idea about working concurrently and simultaneously without fragmentation that could lead to errors. It is expected that by addressing the problem at early stage could assist the designer, manufacturer and constructor to foresee the problem and find the mitigation measures thus could eliminate the errors that may occurs in manufacturing the segment and erection on site.

## ABSTRAK

Pembinaan jambatan menggunakan konsep pemasangan panel segmen pratuang telah menjadi pilihan utama dalam pembinaan jambatan dikawasan tapak yang terhad. Kaedah ini telah mepamerkan kebolehbinaan dalam kawasan bandar, merentasi laluan air, lembah, dan laluan keretapi atau lebuh raya. Kesesuaian kaedah ini bergantung kepada keadaan kawasan tapak kerja, yang menjadi faktor utama dalam pemilihan kaedah ini. Tujuan dan objektif kajian kes ini adalah untuk mengkaji masalah dalam pembuatan panel segmen pratuang dan pemasangan panel tersebut. Projek Sarjana ini mengkaji prosidur pemasangan panel segmen pratuang dengan kaedah *Balance Cantilever* menggunakan *overhead gantry*. Projek ini juga mengkaji prosidur dalam pembuatan panel segmen pratuang dan telah menemui beberapa masalah yang sangat menarik untuk dikaji dan perlu diumumkan kepada pakar-pakar dalam pembinaan jambatan. Kaedah pemasangan juga telah dikaji dan beberapa masalah telah dibangkitkan dan perlu pemerhatian dari pakar-pakar bidang jambatan. Kajian telah dijalankan secara temuduga yang terancang dan soal-selidik dengan pakar-pakar jambatan. Pakar-pakar jambatan dari pihak perunding, pembuat panel segmen, kontraktor utama, kontraktor pakar dalam bidang jambatan dan pakar dalam bidang pra-tegangan telah berkongsi kepakaran teknikal, pengetahuan dan pengalaman masing-masing dalam projek Sarjana ini. Hasil kajian amat menarik dan telah mendedahkan masalah yang berkaitan dan kajian lanjut perlu dibuat. Projek ini juga telah mengemukakan beberapa cadangan kepada pihak-pihak yang terlibat untuk membentuk kerjasama dalam satu pasukan tanpa pembahagian kerja yang rumit. Adalah diharapkan dengan mengenalpasti masalah diperingkat awal dapat membantu pihak yang terlibat mengurangkan kesilapan dalam pembuatan segmen dan pemasangannya.

## TABLE OF CONTENTS

CHAPTER	TITLE	PAGE
	DECLARATION	ii
	DEDICATION	iii
	ACKNOWLEDGEMENTS	iv
	ABSTRACT	v
	ABSTRAK	vi
	TABLE OF CONTENTS	vii
	LIST OF TABLES	xi
	LIST OF FIGURES	xiii
	LIST OF APPENDIX	xvii
<b>1</b>	<b>INTRODUCTION</b>	
	1.1 Background	1
	1.2 Problem Statement	1
	1.3 Objective	5
	1.4 Scope and Limitation	5
	1.5 Brief Research Methodology	6
	1.6 Limitation of the Study	7
<b>2</b>	<b>OVERVIEW OF PRECAST SEGMENTAL BOX GIRDER BRIDGE CONSTRUCTION</b>	

2.1	Introduction	9
2.2	The Historical Background	10
2.3	The Adaptation of the Technology	12
2.4	The Advantages of Segmental Construction	13
2.5	The Disadvantages of Segmental Construction	17
2.6	Alternative Construction Methods	19
<b>3</b>	<b>MANUFACTURING OF SEGMENTAL BOX GIRDER</b>	
3.1	Segmental Box Girder Production	26
3.2	The Concrete Segment	28
3.3	Segment Manufacturing	31
3.3.1	Fabrication of Reinforcement	31
3.3.2	Segment Mould	32
3.3.3	Casting of Segment	34
3.3.3.1	Shortline Match Casting	35
3.3.3.2	Longline Match Casting	35
3.3.4	Geometry Control during Casting	37
3.3.5	Rejection of Segment	38
3.3.6	Handling, Storage and Delivery	40
<b>4</b>	<b>OVERHEAD GANTRY OPERATION AND SEGMENT ERECTION</b>	
4.1	Introduction	43
4.2	Design of the Overhead Gantry	43
4.3	Assembly of the Gantry Launcher	44
4.4	Testing the Overhead Gantry	46
4.5	Segment Delivery	52
4.6	Erection of Segment	54

4.6.1	Erection of Pier Segment	54
4.6.2	Erection of Expansion Joint Segment at Expansion Joint Pier	55
4.7	Launching the Gantry	57
4.8	Epoxy Bonding Agent for Precast Segment	57
4.6.1	Mixing and Application of Epoxy	65
4.9	Stressing Works	68
4.9.1	Temporary Stressing	68
4.9.2	Cantilever Stressing	69
4.9.3	Continuity Stressing	69
4.9.4	Stressing Wire	70
4.10	Concrete Stitching	73
4.11	Tendon Grouting	74
<b>5</b>	<b>RESEARCH METHODOLOGY</b>	
5.1	Introduction	78
5.2	Determination of Research Objective	78
5.3	Literature Review	79
5.4	Data Collections	79
5.4.1	Questionnaire Survey	79
5.4.2	Interview with the Experts	80
5.4.2.1	Objective of the Interview	81
5.4.2.2	Methodology of the Interview	81
5.5	Data Analysis	82
5.5.1	Content Analysis	82
5.5.2	Frequency Analysis	82



	5.5.3	Relative Index Analysis	82
<b>6</b>		<b>ANALYSIS AND FINDING</b>	
	6.1	Introduction	84
	6.2	Questionnaire Survey	85
	6.2.1	Section A – Respondent Back Ground	86
	6.2.2	Section B - Manufacturing of Segmental Box Girder	88
	6.2.3	Section C – Erection of Segmental Bridge	95
	6.3	Analysis of the Structured Interview	102
<b>7</b>		<b>DISCUSSION</b>	
	7.1	Introduction	106
	7.2	Manufacturing of Segment	107
	7.3	Erection of Segment	108
	7.4	New Invention	118
	7.4.1	Transparent Sheath	118
	7.4.2	Ducting Coupler	119
	7.4.3	Stainless Steel Plated Strand	121
<b>8</b>		<b>RECOMMENDATION AND CONCLUSION</b>	
	8.1	The Recommendation	123
	8.1.1	At Inception and Design Stage	123
	8.1.2	At Segment Manufacturing Stage	126
	8.1.3	At Construction Stage	127
	8.2	Conclusion	128
		<b>REFERENCES</b>	129

## LIST OF TABLE

<b>TABLE NO</b>	<b>TITLE</b>	<b>PAGE</b>
2.1	FHWA Condition Ratings for Concrete Bridges	21
2.2	Segmental Concrete Bridge Inspection Report Summary	22
3.1	Segment dimension tolerances	29
4.1	Erection tolerances	60
4.2	Steel wire relaxation loss	72
4.3	Tendon anchorage	73
6.1	Number of respondents	86
6.2	Distribution of the expert respondents based on position	86
6.3	Distribution of Respondent based on experience in bridge construction	87
6.4	Modification on segment as responded in questionnaire	91
6.5	Reinforcement most congested area in segment	91
6.6	Analysis of respond on the contribution factor to problem in manufacturing the segment	93
6.7	Frequency analysis of the factor contribute to problem in manufacturing the segment with Relative Index analysis	94
6.8	Checking on the pier capacity	96
6.9	Modification to pier column	97
6.10	Analysis of respond on the contribution factor to problem in erection the segmental bridge	100
6.11	Frequency analysis of the factor contribute to	101

	problem in erection of segmental bridge with Relative Index analysis	
6.12	Distribution of expertise for interview	102
6.13	Analysis of structured interview with expertise	103
6.14	Frequency analysis on the respond to interview	104

## LIST OF FIGURES

<b>FIGURE NO</b>	<b>TITLE</b>	<b>PAGE</b>
1.1	Research methodology sequence	8
2.1	Nineteenth century cantilever bridge construction (the Firth of Forth Bridge in Scotland)	13
2.2	Precast span-by-span construction with overhead truss (the Spaghetti Bowl in Las Vegas, Nevada)	23
2.3	Cast-in-place span-by-span construction with self- launching forms (Rosario Victoria Bridge in Argentina)	23
2.4	Incrementally launched deck for Neckarburg Arch Bridge in Germany, 1977	24
2.5	Vietnam Veterans Memorial Bridge - cantilever construction of a segmental box girder using traveling forms	24
2.6	Typical shape of box girder on pier for Subang Kelana Link Project	25
3.1	Arrangement of the segment between intermediate piers	30
3.2	The rebar jig where the reinforcement is being fix	31
3.3	Reinforcement arrangement in the segment at the left and right web area	32
3.4	Reinforcement at center web with blister	33
3.5	Schematic diagram for curing cell for SKL Project	36
3.6	Longline casting yard	36
3.7	Arrangement of the segment's marking	38
3.8	Typical segment shape	39

3.9	Sand blasting to the match-cast surface of the segment	41
3.10	Straddle carrier being used to shift the segment within casting yard	42
4.1	Typical gantry launching steps	45
4.2	Preparing the hardstand for gantry assembly near P13 and P12 at Subang Kelana project	47
4.3	Part of the gantry being assembled at Bayan Baru bypass Project	47
4.4	Schematic figure for step by step gantry assembly	49
4.5	Schematic figure for step by step gantry assembly	50
4.6	Schematic figure for step by step gantry assembly	51
4.7	Deflection checking point on the gantry truss	52
4.8	Load testing for the complete assembled gantry prior to segment erection to a 1.5 factor of safety	53
4.9	Arrangement of segment delivery	53
4.10	Pier segment being arrange to be seated on the jacks	55
4.11	Schematic figure on the segment seating	55
4.12	Sequence of segment erection at expansion joint	58
4.13	Sequence of segment erection at intermediate piers	59
4.14	Launching step 1 & 2	61
4.15	Launching step 3	62
4.16	Launching step 4	62
4.17	Launching step 5 & 6	63
4.18	Launching step 7	63
4.19	Launching step 8	64
4.20	Mixing the epoxy bonding agent	66
4.21	Applying the epoxy onto the segment surface	67

4.22	Temporary stressing using stress bar	69
4.23	The tendon stressing anchorage	70
4.24	Stressing step by step	71
4.25	Stressing in progress	71
4.26	Schematic diagram of the stitch	74
4.27	Stitch beam installed and stress to align the box girder	75
4.28	Concreting the stitch in progress	75
4.29	Typical arrangement of the tendon in prestress structure	76
6.1	Distribution of respondent based on position	87
6.2	Distribution of Respondent based on experience in bridge construction for questionnaire	88
6.3	Distribution of respondent for interview	102
7.1	One of massive modification by contractor to cater for extra construction load	111
7.2	Close up of the above at the middle and left of the segment	111
7.3	Transverse pre-stressing for one of the segment as design by specialist contractor to cater for extra load	112
7.4	Pier segment temporarily seated on jacks. Load transferred to pier eccentrically	112
7.5	Temporary blister at middle of segment for temporary prestressing	113
7.6	Temporary blister at both left & right of the web for temporary prestressing	113
7.7	The temporary staging for erection of half end of segment at expansion joint pier design by contractor	114
7.8	The temporary staging from front view	115
7.9	Temporary nailing (tie down) pier segment to the pierhead	116
7.10	Transparent sheathing used for external tendon in Japan	119
7.11	The Liaseal Coupler	120

7.12	Schematic drawing of the Liaseal Coupler	120
7.13	Drawing illustrated cross-section details of Liaseal duct Coupler	121
7.14	DSI Stainless steel plated strand	122

**LIST OF APPENDICES**

<b>APPENDIX</b>	<b>TITLE</b>	<b>PAGE</b>
A	Questionnaires for the Thesis	133



## CHAPTER 1

### INTRODUCTION

#### 1.1 Background

Bridge construction using the precast post tension segmental box girder is considered a new trend in Malaysia. This method of construction started with construction of Light Rail Transit (LRT) viaduct in 1997, post tension box girder start to gain recognition as a preferred method of construction of bridge within the urban area. This similar construction follows by construction of Second Link Bridge to Singapore, Bayan Baru By-pass, Butterworth Offshore ring Road, several bridges in Kuala Lumpur such as Ampang-Kuala Lumpur Elevated Highway, SPRINT Highway, Kerinci Link, New Pantai Expressway, Subang Kelana Link and so on. The constructed box girder bridge has been utilizing several methods such as Span-by-Span, Balanced Cantilever and Incremental Launching. This master project explores the process of manufacturing the segmental box girder and the construction/erection of the post tension precasted segmental box girder bridge using balance cantilever method.

#### 1.2 Problem Statement

During the design stage, in normal practice, the main consultant design normally will cater for permanent structure only. Any design for temporary work such as temporary pre-stressing, segment modification, additional blister, check for segment lifting, check for segment's reinforcement for additional load, thickening of

top slab, etc, being carried out by the contractor and / or bridge specialist contractor. The process of preparing shop drawing, review by consultant, resubmitting the revised shop drawings, getting the shop drawing endorsed by Professional Engineer always take a few round and time consuming before it could be approved and use for manufacturing the segment.

During segment production at casting yard, the problems arise in fabricating the mould and reinforcement. Due to short size of the segment, longitudinally, the reinforcement become congested, the reinforcement may collide with the tendon conduit and other insertions item. The reinforcement also clashes between them and the gap is very close, make it limited access for concrete to fill up the formworks. Wollman *et. al.* (2000) reported that the end diaphragm segment where the tendon is anchored, which is also the Pier Segment always experience the cracks occurred. One of the reason mentioned is due to detailing of the congested reinforcement which limited the access of the concrete to compact, thus created a localise improper and incomplete compaction to the concrete. This phenomenon created the crack when stressing applied to the tendon.

FHWA (2005) in their Task Number 7.11 – Proper Detailing had addressed the common problem in detailing of the segment that result in problem during casting such as:

1. Reinforcing fit-up. Conflicts can occur at anchorages, blisters, deviation beams and bearing diaphragms. The three-dimensional space requirements of tendon anchors and spirals need to be accounted for. Reinforcing should be arranged to accommodate horizontal and vertical tendon profiles. All reinforcing bends with the actual curve radius should be drawn to scale.
2. Nodes. All tensile reinforcing entering a structural node (Strut & Tie design) should be adequately developed. Post-tensioning bars require some distance from the free, perpendicular edge to become developed; cover requirements, bar extension, nut and plate thickness can combine to shift a node off of the center of the neutral axis of an entering thin wall element (e.g. web or slab entering a diaphragm).

3. Appurtenances. Details for access openings, drains, lighting fixtures etc. are often presented as separate details at the end of a plan set. These too should be drawn to scale with the reinforcing from typical plan sheets prior to final plan preparation. In complex projects, fully-integrated drawings may be necessary. Access hatches should swing free of external tendons, plumbing etc. Plumbing should be positioned so that it creates the least interference with passageways in the box. Additional reinforcing should be added if the element creates a disturbance in the flow of forces.
4. Short tendons. Post-tensioning bars should be used if the losses in short tendons are too great.
5. Tolerances. Details need to be buildable by conventional practices. A large, circumferential stirrup that engages both webs and flanges may need to be spliced into two telescoping U-shaped bars. Cast-in-place closures joining two soon-to-be prestressed elements should be wide enough to accommodate precast duct misalignments.
6. Jack Fit-Up. Hydraulic ram dimensions and stroke need to be accounted for when locating tendon anchors within the box.
7. Water Control. Methods to control water from broken plumbing and expansion joint seals should be integrated into the design. Holes cast into the bottom slab adjacent to bearing diaphragms and deviation beams will both remove the water from the box and serve as a tattletale for maintenance inspectors. These holes can easily be clogged with construction debris or grout and should be cleared before the contractor finishes the project. Transverse drip beads on the web and underside of the wings located one inch from the expansion joint should contain the longitudinal spread of stains resulting from a broken seal. Unsightly column staining can be controlled with either creative column detailing to channel water or an umbrella (drip pan) perched on top.

8. Temporary Drain Caps. Plans should specify a temporary plumbing line cap at the top of the column to discourage solid waste disposal by construction personnel.
9. Critter Guards. Roosting birds and varmints need to be kept out of the girder. Expanded metal mesh mounted to a metal frame on the inside circumference of the box (i.e. oriented in the planes of the webs and flanges) at expansion joints has worked well. Transverse screens impede movement of maintenance personnel through the box and should be avoided.
10. Future Post-Tensioning. During the design of the very first segmental bridges, long-term moment redistribution was an unknown phenomenon. To counteract unexpected deflections, additional post-tensioning was added after the bridges were in service. This was accomplished with some difficulty. Today the more likely cause of future additions of post-tensioning (although this is very rare in a well-detailed bridge) is from tendon corrosion. Bridge designs of today should have provisions for easily adding supplemental post-tensioning. Casting additional, empty post-tensioning anchorages and deviation pipes into diaphragms is the most common method. Allowances need to be made for transporting and positioning hydraulic stressing rams inside the bridge.

Problem during construction is expected when the segment is delivery. For erection using the gantry launcher, assembling the gantry takes more than two months, the kinematic drawing for gantry movement during launching should be prepare for every span. During tendon stressing, the tendon may fail to achieve the calculated elongation. The segment erected might be difficult to set at design level and alignment. After stressing, the tendons need to be grouted. The grout materials shall comply with stringent specification in order to ensure the grout filled up the whole tendon conduit.

### **1.3 Objective**

The aim of this master project is to study the system of the construction of post tension precast box girder bridge using gantry launcher by Balance Cantilever method.

The objectives of this master project are:

1. To determine the problems in manufacturing/fabricating the segmental box girder at casting yard before deliver to site.
2. To determine the problem in precast segment erection/construction using the overhead gantry launcher at site.
3. To propose the strategy for coordinated design procedure between consultant and specialist contractor.

### **1.4 Scope and Limitation**

This master project focused on the construction of bridge using precast segmental box girder. The study is subjected to the following scopes and limitation:

1. This study is limited to the manufacturing of the segment by the short line match-casting method.
2. The study is limited to the bridge construct using Post Tension Precasted Segmental Box Girder erected using the gantry launcher by Balanced Cantilever method.

Even though there are several method of construction of bridge for segmental bridge, but the other method does not affected the modification of the segment and structure.

### **1.5 Brief Research Methodology**

The methodology used in conducting this research is through literature search, structured interview with selected personnel that have direct involvement with the manufacturing and erection of the segment and questionnaire survey among the other person involved. The literature search explored the system used in constructing the segmental bridge by Balance Cantilever Method as well as other method available, advantages and disadvantages of the bridge construction method, the history of it and the problem faced by the works that have been establish somewhere else. Literature review is referred to the published journal, technical paper and relevant book on the design, related and reliable website regarding the construction, management and maintenance of the bridge.

The questionnaire survey has been conducted among the selected person from the segment manufacturer and contractors in Malaysia to establish the problem they faced in manufacturing the precast segment and erection of the segmental bridge using the gantry launcher. A structured interview also has been conducted with the segment manufacturer, contractors, consultant and the consultant's representative at site to seek their opinion and suggestion on how to improve the construction procedures. The data compiled are analysed using simple frequency method and Relative Index Analysis. Figure 1.1 shows the research methodology procedure and sequence in this study.

Based on the analysis and finding, several recommendation have been made in according to the objective that have been set off earlier. The recommendation represent constructive proposals and suggestions on how to eliminate or at least

minimise the problem that have been determine, thus could also eliminate the problem that may occurs during operation and maintenance.

### **1.6 Limitation of the study**

The limitation of the study is confined to construction of segmental box girder bridge that being built in Malaysia by Balance Cantilever method only. Even though there is several method of construction for segmental bridge such as span-by-span, incremental launching, cast-in-situ segmental and normal cast-in-situ, but these method do not involved modification carried out to the segmental box girder and pier and no checking need to be done by contractor. The final construction drawing has been incorporated all the designs and construction requirement by consultant.




Figure 1.1 Research methodology sequence



## REFERENCES

American Segmental Bridge Institute (2006). *Grouting Recertification*, American Segmental Bridge Institute Magazine (SEGMENTS) Vol. 47, Winter.

Andrew C., Raymond S. (2006). “*Method Statement for Segment Erection*”, VSL Engineers Sdn Bhd & Projalma Sdn Bhd JV (VPJV), Subang Kelana Link Project. unpublished

Arthur M. P. (2004). “*Precast Segmental Casting Yards: Past, Present And Future*”, PB Networks Online Magazine, Issue No. 57, Vol. XIX, Number 1. Feb. Website: <http://www.pbworld.com>

Cliff F. ed. (2006). “*Design and Construction of Segmental Concrete Bridges for Service Life of 100 to 150 Years*”, American Segmental Bridge Institute Magazine (SEGMENTS) Vol. 47, Winter.

Federal Highway Administration (2003). “*Task 15.2 Research Synthesis Statement: Segmental Concrete Bridge Design and Construction Practices.*” Washington D.C., Federal Highway Administration, U.S. Department of Transportation. Website <http://fhwa.dot.gov/BRIDGE/segmental/task15.2.htm>

Federal Highway Administration (2003), “*Segmental Concrete Bridge Technology – Is a Segmental Bridge Right for You?*” Federal Highway Administration, U.S. Department of Transportation. Website : <http://fhwa.dot.gov/bridge/segmental/right.htm>

Federal Highway Administration (2003), “*Segmental Concrete Bridge Technology – Is a Segmental Bridge Right for You?*”, Federal Highway Administration, U.S. Department of Transportation.

Website : <http://fhwa.dot.gov/bridge/segmental/right.htm>

Frank B., Scott W. D. (1997), “*Fast Track Segmental Concrete Bridge*”, PB Networks Online Magazine, Issue No. 38, Vol. XI, Number 2. Spring,

Website: <http://www.pbworld.com>

Gunnar L., Jesus M.de la Garza. (2003). “Constructability Consideration for Balanced Cantilever Construction”, *Journal Practice Periodical on Structural Design and Construction*, Feb, pg 47-56.

Joseph K. T. (2004). “*Considering Segmental Concrete Bridge*”, PB Networks Online Magazine, Feb, Issue No. 57, Vol. XIX, Number 1.

Website: <http://www.pbworld.com>

Juan A. M., Joseph I. S. (2004). “*Brief History of Segmental Concrete Bridge Construction*”, PB Networks Online Magazine, Feb, Issue No. 57, Vol. XIX, Number 1.

Website: <http://www.pbworld.com>

Juan A. M. (2004). “*Advantages of Segmental Construction*”, PB Networks Online Magazine, Feb, Issue No. 57, Vol. XIX, Number 1.

Website: <http://www.pbworld.com>

Lee K. M., Raymond S. (2005) “*Method Statement for Precast Segment Manufacturing*”, VSL Engineers Sdn Bhd & Projalma Sdn Bhd JV (VPJV), Subang Kelana Link Project. unpublished.

LoBuono, J. (2005). “ *Assembly required – The instruction for building New Jersey’s first segmental bridge.*” Chicago, Illinois: BridgesMagazineOnline.com Sept/Oct.

Website : <http://www.brisgebuildermagazine.com/>

Low S. P., Choong J. C. (2001) “Just in Time Management of Precast Concrete Components”, *Journal of Construction Engineering and Management*, Nov/Dec.

Maurice D. M. (2001). “Durability of Segmental Concrete Bridges” *Journal of Bridge Engineering*, Vol. 6, No. 6, November/December, pg.539-542.

Poh B. S., Raymond S. (2006). ”*Method Statement for Gantry Assembly*”, VSL Engineers Sdn Bhd & Projalma Sdn Bhd JV (VPJV), Subang Kelana Link Project, April. unpublished.

Public Works Department of Malaysia (2004), *Contract Document, Volume II, Specification - Section 16, “Segmental Construction”* for Projek Membina Jalan Penyambung Subang Kelana, Public Works Department of Malaysia (PWD), Road Division, Special Project Unit.

Raymond S., Lee K. M. (2005). “*MS PowerPoint Presentation for segment fabrication at Casting Yard, Batu Gajah, Perak*”, VSL Engineers Sdn Bhd & Projalma Sdn Bhd JV (VPJV) July . unpublished.

Raymond S., (2005). “*MS PowerPoint Presentation for segment erection*”. VSL Engineers Sdn Bhd & Projalma Sdn Bhd JV (VPJV), July. unpublished.

Richard M. B., Mark L. H., Martha C. (2002), “50-year-old prestressed segmental concrete bridge”, *Journal of Professional Issues in Engineering Education and Practice*, April, pg 83-87

Poston R.W., Wouters J.P. (1998). “*Durability of Precast Segmental Bridges*” *Final Report for National Cooperative Highway Research Program*, Transportation Research Board, National Research Council, United State of America, June.

Wollman G. P., Breen J. E., Kreger M. E. (2000). “Anchorage of External Tendon in End Diaphragms”, *Journal of Bridge Engineering*, August, pg 208-215

Vijay C., Peter A., Paul J. T. (2004), “*South Bay Interchange: New Frontiers in Segmental Construction*”, PB Networks Online Magazine, Feb, Issue No. 57, Vol. XIX, Number 1.

Website: <http://www.pbworld.com>

VSL Far East (2005) “*Post tensioning Systems*”, VSL Engineering Pte. Ltd., Hong Kong.