

KEY FACTORS AFFECTING THE ADAPTATION OF PREFABRICATED
PREFINISHED VOLUMETRIC CONSTRUCTION (PPVC) IN MALAYSIA
INDUSTRY

LOH SENG YAP

A project report submitted in partial fulfilment of the
requirements for the award of the degree of
Master of Engineering (Construction Management)

School of Civil Engineering
Faculty of Engineering
Universiti Teknologi Malaysia

JANUARY 2019

DEDICATION

This project report is dedicated to my beloved family and friends for their endless support and encouragement.

ACKNOWLEDGEMENT

First and foremost, I would like to express sincere gratitude and appreciation to my supervisor Dr. Eedyzah Aminudin for her noble guidance and valuable advice, as well as her incredible understanding and capability to initiate guideline without being overbearing. Without her, this project report will not become reality.

I owe a great many thanks to all parties whom had given me encouragement, assistance and permission to collect all the data and details during the writing of this project report directly or indirectly.

I also would like to take this opportunity to express gratitude to all my friends, colleagues and my fellow postgraduate students for their enormous help in collecting the surveys and their participation in the questionnaires. Sincere gratitude and appreciation goes to all developers, consultants, manufacturers/suppliers and contractors who participated in this research. A special thanks to the panel of experts for their contribution and valuable opinion.

Finally, to my family member especially my wife, a very special thank you for her sacrifices, patience, love and support throughout my study period.

ABSTRACT

Prefabricated Pre-finished Volumetric Construction (PPVC) is the advanced modular construction technology introduced by Singapore Building and Construction Authority (BCA) to promote a modern practices in construction sector which rectifying the fragmentation of construction industries towards higher productivity and more efficiency in project delivery. PPVC is an innovative approach to replace the traditional on-site construction method which construct a building using modular units away from the physical site but into a controlled factory environment. The adoption of PPVC has a significant solution to tackle the current level of quality, workmanship, productivity, non-environment construction, unaffordable housing, lacking on-site safety awareness, construction wastage and excessive reliance on unskilled foreign labors associated with conventional construction methods. In Malaysian, PPVC still lagging far behind in the development of Malaysian construction industry. The effectiveness of using PPVC can reduce the number of on-site contractors, increase the efficiencies in the use of resource and minimize the construction waste as well as reduce the overall of construction cost and durations. As a result, the aims of this study are to investigate the key factors affecting the adaptation of PPVC in Malaysia Construction Industry and thus recommend a criteria of feasible mitigation strategies in order to increase the possibility of using PPVC in the future development of Malaysian industry. To achieve these goals, questionnaire was administered by goggle survey form and distributed to industry experts who had working experience in the building industry. A total of 63 responses was received in this survey. Lastly, the results showed that highest number of respondents agreed that the effectiveness of using PPVC were “reduce the overall construction time”, “reduce on-site manpower and equipment requirement”, “better quality of workmanship, efficiency and productivity”. Results also implied that the top three important factors were “lacking experiences of current contractors, subcontractor on PPVC method”, “lacking PPVC of design experience, technical & installation” and “require high operation for capacities of heavy lift crane”. It also revealed the three effective mitigation strategies were “the use of Building Information Modelling (BIM) to tackle the building modular construction and coordination”, “intense coordination to ensure work sequence with minimal delays” and “early involvement of contractors and suppliers / manufacturers during the design phase of the project”. Moreover, there are significant risk on using PPVC as the reliability is much harder to guarantee than conventional construction method. PPVC can be very beneficial to a project, but only if everyone involved has the proper experience and ability to perform such activities. This study contributes to industry practitioners to enhance their understanding of PPVC in order to increase the affordability and sustainability of houses in the future development of Malaysian industry.

ABSTRAK

Kaedah pembinaan volumetrik prafabrikasi prasiap (PPVC) merupakan teknologi pembinaan modular canggih yang diperkenalkan oleh Pihak Berkuasa Bangunan dan Pembinaan Singapura (BCA) untuk mempromosikan amalan moden dalam sektor pembinaan yang membetulkan pemecahan industri pembinaan ke arah produktiviti yang lebih tinggi dan kecekapan dalam penghantaran projek. PPVC adalah pendekatan inovatif yang menggantikan kaedah pembinaan unit modular secara tradisional di tapak kepada persekitaran kilang yang terkawal. Penerapan PPVC mempunyai penyelesaian yang penting untuk menangani tahap mutu, mutu kerja, produktiviti, pembinaan bukan persekitaran, perumahan yang tidak boleh dibiayai, kurang kesedaran keselamatan di tapak, pembaziran pembinaan dan pergantungan yang berlebihan terhadap tenaga kerja asing yang tidak mahir yang dikaitkan dengan kaedah pembinaan konvensional. Di Malaysia, PPVC masih jauh ketinggalan dalam pembangunan industri pembinaan di Malaysia. Keberkesanan penggunaan PPVC dapat mengurangkan jumlah kontraktor di tapak, meningkatkan kecekapan dalam penggunaan sumber dan meminimumkan sisa pembinaan serta mengurangkan keseluruhan kos pembinaan dan jangka masa. Oleh itu, matlamat kajian ini adalah untuk menyiasat faktor utama yang mempengaruhi penyesuaian PPVC di Industri Pembinaan Malaysia dan mencadangkan kriteria strategi mitigasi yang sesuai untuk meningkatkan kemungkinan penggunaan PPVC dalam pembangunan industri Malaysia pada masa akan datang. Untuk mencapai matlamat ini, soal selidik ditadbir oleh borang tinjauan goggle dan diedarkan kepada pakar industri yang mempunyai pengalaman kerja dalam industri pembinaan. Sebanyak 63 respons telah diterima dalam tinjauan ini. Akhir sekali, keputusan menunjukkan bahawa bilangan responden tertinggi bersetuju bahawa keberkesanan penggunaan PPVC "mengurangkan masa pembinaan keseluruhan", "mengurangkan keperluan tenaga kerja dan peralatan di tapak", "kualiti kerja, kecekapan dan produktiviti yang lebih baik". Hasilnya juga menyatakan bahawa tiga faktor utama yang dihadapi adalah "kurang pengalaman kontraktor semasa, subkontraktor dalam kaedah PPVC", "kurang pengalaman reka bentuk PPVC, teknikal dan pemasangan" dan "memerlukan operasi yang tinggi untuk kapasiti kren angkat berat". Ia juga mendedahkan bahawa tiga strategi mitigasi yang berkesan ialah "penggunaan Pemodelan Maklumat Bangunan (BIM) untuk menangani pembinaan dan penyelarasan modular bangunan", "penyelarasan sengit untuk memastikan urutan kerja dengan kelewatan yang minimum" dan "penglibatan awal kontraktor dan pembekal / pengeluar semasa fasa reka bentuk projek ". Selain itu, terdapat risiko yang signifikan untuk menggunakan PPVC kerana kebolehpercayaan lebih sukar untuk menjamin daripada kaedah pembinaan konvensional. PPVC boleh memberi manfaat kepada sesuatu projek, tetapi hanya jika semua orang yang terlibat mempunyai pengalaman dan keupayaan untuk melaksanakan aktiviti tersebut. Kajian ini menyumbang kepada para pengamal industri untuk meningkatkan pemahaman mereka terhadap PPVC dalam rangka meningkatkan kemampuan dan kelestarian rumah di masa depan pembangunan industri Malaysia.

TABLE OF CONTENTS

TITLE	PAGE
DECLARATION	ii
DEDICATION	iii
ACKNOWLEDGEMENT	iv
ABSTRACT	v
ABSTRAK	vi
TABLE OF CONTENTS	vi
LIST OF TABLE	xi
LIST OF FIGURES	xii
LIST OF ABBREVIATIONS	xiii
LIST OF SYMBOLS	xiv
LIST OF APPENDICES	xv
CHAPTER 1 INTRODUCTION	1
1.1 Introduction	1
1.2 Problem Statement	4
1.3 Aim and Objectives	5
1.4 Scope of Work	5
1.5 Significant of Study	6
CHAPTER 2 LITERATURE REVIEW	7
2.1 Introduction	7
2.2 Timeline improvement of Building Industrialization in Malaysia	8

2.3	Configuration of Prefabricated Pre-finished Volumetric Construction	9
2.4	Requirement in PPVC system	12
2.5	Effectiveness of using PPVC method	13
2.5.1	Reduce the overall cost	14
2.5.2	Reduce the overall construction time	14
2.5.3	Produce less construction waste, dust and pollution	16
2.5.4	Reduce on-site manpower and equipment requirement	16
2.5.5	Quality of workmanship, efficiency and productivity	16
2.5.6	Reduce risks related to occupational safety and health	17
2.5.7	Increase profitability of the industry due to economy of manufacturing scale	17
2.4.8	Less congestion on site through minimization of on-site operations	18
2.5.9	Flexible performance for reuse, movable, deconstruction and refurbishment	18
2.5.10	Reduce and limit construction noise	19
2.5.11	Improve environmental impact in sustainable building design	19
2.5.12	Weatherproof construction–not depending on climate conditions	19
2.5.13	Produce more affordable housing in future development	20
2.6	Factors affecting the adaptation of PPVC method	20
2.6.1	Political factors	22
2.6.2	Market factors	22
2.6.3	Economic factors	23
2.6.4	Environmental & technological factors	24
2.6.5	Social factors	25

2.7	Mitigation strategies faced in the adaptation of PPVC method	25
2.7.1	Mitigation strategies for governance by cost	27
2.7.2	Mitigation strategies for governance by process	28
2.7.3	Mitigation strategies for organizational by cost	29
2.7.4	Mitigation strategies for organizational by process	30
2.7	Summary	30
CHAPTER 3	RESEARCH METHODOLOGY	31
3.1	Introduction	31
3.2	Research design	31
3.3	Methodology flowchart	32
3.4	Questionnaire design	33
3.5	Data analysis methods	33
3.5.1	Analysis of Variance (ANOVA) method	33
3.5.2	Severity Index (SI) method	34
CHAPTER 4	DATA ANALYSIS AND RESULTS	35
4.1	Introduction	35
4.2	Questionnaire respondents	35
4.3	Respondents' perceptions of using (PPVC) method	38
4.4	Reliability analysis	41
4.5	Objective 1: The effectiveness of using PPVC method	42
4.6	Objective 2: The factors affecting the adaptation of (PPVC) method in Malaysia Construction Industry	43
4.7	Objective 3: Mitigation strategies faced in the adaptation of PPVC method	46
4.8	Mitigation strategies for the factors faced in adopting (PPVC) method	50
4.9	Discussion: The important levels of factors within their associated categories	51

4.10	Discussion: The important levels of mitigation strategies within their associated criteria	53
4.11	Effect of respondents' working experience on the results	55
4.12	The Current gaps for all respondents' opinion of the adaptation of PPVC in Construction Industry	58
4.13	The Current gaps for respondents' with less than 10 years of working experience opinion of the adaptation of PPVC in Construction Industry	59
4.14	The Current gaps for respondents' with over than 10 years & 20 years of working experience opinion of the adaptation of PPVC in Construction Industry	60
CHAPTER 5	CONCLUSION AND RECOMMENDATION	61
5.1	Introduction	61
5.2	Conclusion – Objective 1	61
5.3	Conclusion – Objective 2	62
5.4	Conclusion – Objective 3	62
5.5	Recommendation	63
5.6	Summary	64
REFERENCES		65
APPENDICES		71

LIST OF TABLE

TABLE NO.	TITLE	PAGE
Table 1.1	The categorization of building industrialization in Malaysia Industry	8
Table 2.1	Requirement in PPVC system	12
Table 2.2	References for factors affecting the adaptation of (PPVC) method	21
Table 2.3	References for mitigation strategies faced in adopting (PPVC) method	26
Table 3.1	Research design	32
Table 4.2	Respondents' Particular Information and Detail	37
Table 4.4	Reliability Statistics for Factors and Mitigation Strategies	42
Table 4.5	The Effectiveness of using (PPVC) method	42
Table 4.6	The factors affecting the adaptation of (PPVC) method in Malaysia Construction Industry	43
Table 4.7	Mitigation strategies faced in adopting (PPVC) method in Malaysia Construction Industry	46
Table 4.8	Mitigation strategies for factors faced in adopting (PPVC) method	50
Table 4.9	The important levels of factors within their associated categories	51
Table 4.10	The important levels of mitigation strategies within their associated criteria	53
Table 4.11	Impact of the participants' working experience on the rank of the factors	55
Table 4.12	Impact of the participants' working experience on the rank of the mitigation strategies	55

LIST OF FIGURES

FIGURE NO.	TITLE	PAGE
Figure 1	Evolution of Off-Site Construction Industry (Azman et al. 2010)	9
Figure 2	Typical of 2-Bedroom Unit Modular in Plan View	10
Figure 3	Typical of 2-Bedroom Unit Modular in 3D View	11
Figure 4	Time saving in PPVC method (adapted from Kamali & Hewage, 2016)	15
Figure 5	Factors falling into 5 categories	20
Figure 6	Governance and organizational by cost & process criteria	26
Figure 7	Profile of the respondents' institution	36
Figure 8	Respondents' year of experience involve in IBS/PPVC	36
Figure 9	Respondents' perceptions 1	38
Figure 10	Respondents' perceptions 2	39
Figure 11	Respondents' perceptions 3	39
Figure 12	Respondents' perceptions 4	40
Figure 13	Respondents' perceptions 5	40
Figure 14	Framework of current gaps for all respondents' opinion of the adaptation of PPVC in Construction Industry	58
Figure 15	Framework of current gaps for respondents' with less than 10 years of working experience opinion of the adaptation of PPVC in Construction Industry	59
Figure 16	Framework of current gaps for respondents' with over than 10 & 20 years of working experience opinion of the adaptation of PPVC in Construction Industry	60

LIST OF ABBREVIATIONS

ANOVA	-	Analysis of Variance
BCA	-	Building and Construction Authority, Singapore
CIDB	-	Construction Industry Development Board Malaysia
CIMP	-	Construction Industry Master Plan
CITP	-	Construction Industry Transformation Programme
IBS	-	Industrialised Building System
PPVC	-	Prefabricated Pre-finished Volumetric Construction
QLASSIC	-	Quality Assessment System in Construction
SI	-	Severity Index
SPSS	-	Statistical Product of Service Solution

LIST OF SYMBOLS

n	-	Total Number of the completed questionnaires
f_i	-	Total frequency of the score
n	-	Total Number of the completed questionnaires
w_i	-	Weight of the assigned score

LIST OF APPENDICES

APPENDIX	TITLE	PAGE
Appendix A	Questionnaire form	71
Appendix B	SPSS analysis results attachment	82

CHAPTER 1

INTRODUCTION

1.1 Introduction

Prefabricated Pre-finished Volumetric Construction (PPVC) is a new construction approach where building components are assembled into room-sized volumetric units off-site in a controlled factory environment (Jiang et al., 2018), and then transported on-site and stacked on top of each other to form a complete building. Modular components are characterized as a three dimensional object whereby its size is to provide utility space. Each modular component includes floor, walls, frame, ceiling and other accessories fitting (Kyjakova & Baskova, 2016). PPVC method is a fast evolving as an effective alternative compared to conventional construction method and it has been widely adopted in Japan, parts of Europe and North America.

Prefabricated Prefinished Volumetric Construction (PPVC) is known as Modular Construction technology in Malaysia which had been well-applicable in constructing commercial buildings around the world for decades (Ong Ying Rui & Khairulzan Yahya, 2016). Modular technology significantly speeds up construction, improves productivity in terms of manpower and time savings. In a nutshell, lower costs and shorter construction period with better quality are the core values implemented in every construction projects (Ong Ying Rui, Khairulzan Yahya, 2016). Building and Construction Authority, Singapore (BCA) is strongly promote off-site prefabricated for on-site assembly and encouraging more local corporates to focus on greater adoption of PPVC technology as well as productive technologies. Today, Singapore has developed the world's tallest of 40 storey PPVC condominium with concrete modular. In addition, Singapore is the most productive residential construction projects in the world due to its outcome-based regulation.

According to The Construction Industry Transformation Programme (CITP) 2016-2020 which envisions the Malaysian industry to become an advanced, continued growth of national collaborative, nurture international champions with the aim of success in Malaysian construction industry. To achieve these outcome, four strategic thrusts have been identified by CITP which were subsequently formed a clear key across each of the four strategic. The four (4) strategic thrusts are:

- i. To deliver an industry culture which ingrained with professionalism, safety and quality.
- ii. Malaysia will be a model for the emerging world in terms of sustainable infrastructure.
- iii. The construction industry will more than double its productivity, and the increase in productivity will be matched by higher wages.
- iv. Malaysian construction industry champions will be nurtured, and will lead the charge both locally and globally.

First strategic thrust of CITP aims to improve the quality standards of Malaysian construction industry. To achieve this vision, CITP emphasises on the implementation of the Quality Assessment System in Construction (QLASSIC). QLASSIC can be used to measure the quality of workmanship in building construction which serve as broader quality assurance based on the Standard of Building Requirement. However, to obtain high scores in QLASSIC through project that using conventional construction method are very difficult. To obtain higher QLASSIC scores, CITP encourage the adoption of new technology such as PPVC adoption to enhance precision of material and workmanship. Furthermore, CITP puts more effort on safety levels in the industry. There will be more stringent requirements on occupational safety and health implement in construction industry as well as standards and Codes of Practice which can governing construction safety and health. To achieve this mission, the PPVC adoption will enable to more control over the construction safety and health since building components are manufactured at the controlled factory. Workplace accidents and dangerous construction works can be minimized by transferring the main construction work to controlled factory environment.

Second strategic thrust of CITP that Malaysia's environmentally sustainable construction to be a model for the emerging world. To drive sustainable construction excellence in the industry, rating tools will be developed with incentive programmes to encourage sustainable projects. To achieve this mission, the PPVC adoption is mandatory to drive changes in current construction market to pursue long term environmentally sustainable practices to produce Malaysia as a low carbon and sustainable country. The adaptation of PPVC in the Malaysian Construction Industry is proven to improve productivity and promote sustainability of the construction industry (Musa M.F and Mohammad M.F, 2015). In addition, the adoption of PPVC produce less construction waste will be achieve in lower CO₂, more resilient, resource-efficient, and socially-inclusive manner.

Third strategic thrust of CITP that measures to raise productivity levels. In current of construction industry, low productivity level which reflect the construction participant's demand to adopt new technology and practice which results less high-skilled or construction experts in construction industry. However, for the new construction technology such as PPVC adoption, the construction workforce will be highly capable as well as the potential of increase skilled local workforce into the industry (CITP, 2016-2020).

Fourth strategic thrust of CITP aims for the performance of local construction participation to meet expected international standards. These visions are implement of internationalize practices and standards which includes the adoption of higher material standards and specifications. With the introduce Malaysian Standard for construction specifications will help to enhance and expand in facilitating the new technology such of PPVC. In addition, the create of nationwide standardization for PPVC method include the accreditation, quality check/assurance, modular coordination, standardized design components, codes and guidelines will allow fluently practice the PPVC adoption and its processes.

1.2 Problem Statement

Housing is the basic requirement of every human being. Due to the faster-growing population, and to fulfill the tremendous housing demand, a more affordable, faster, reliable, sustainable method of construction is deemed necessary in a developing countries such as in Malaysia construction industry. In current level of Malaysia industry, the issues of quality, workmanship, productivity, non-environment construction, unaffordable housing, lacking on-site safety awareness, construction wastage and excessive reliance on unskilled foreign labors which associated with conventional construction method. Although CIDB had introduced the Construction Industry Transformation Programme (CITP) 2016-2020 that measures to enhance and modernize the construction productivity by adopting of relevant technology such IBS technology / pre-fabrication in project planning. However, the adoption of improved construction technology such as PPVC still unexplored. To enhance the performance of the construction industry, Malaysian industry has to move towards industrialization by adopting PPVC, to replace from conventional construction method to the modern construction method as well as to improve the sustainability of the construction industry. Moreover, PPVC adoption will savings on the overall cost and on-site labor cost (Kamali and Hewage, 2016). In this direction, it could able to build more affordable residential houses in future development.

Despite there are many well-documented benefit that PPVC has an effective alternative to conventional construction method, and PPVC has widely gain acceptance into global construction community. However, it indeed a tough task for Malaysian Construction Industry in adopting a new technological innovation. Yet, much of the factors limiting the PPVC adoption in Malaysia. Country such as Singapore has successfully widely adoption of prefabricated pre-finished volumetric construction (PPVC), resulting in overall good performances compared to conventional on-site construction method (HDB, 2011). PPVC adoption also reducing compliance cost in the way of making more affordable housing project and realize cost effective. Therefore, this study is significant to improve the Malaysia industry move into positive transformation aimed to adopting PPVC construction method in order to increase the affordability and sustainability of houses in the near future development.

1.3 Aim and Objectives

The aim of this project report is to study the current gaps of adaptation of Prefabricated Prefinished Volumetric Construction (PPVC) in construction industry. The following objectives have been identified are:-

- (a) To study on the effectiveness of using Prefabricated Prefinished Volumetric Construction (PPVC) method in Malaysia Construction Industry.
- (b) To determine the factors affecting the adaptation of Prefabricated Prefinished Volumetric Construction (PPVC) method in Malaysia Construction Industry
- (c) To recommend the mitigation strategies faced in adopting Prefabricated Prefinished Volumetric Construction (PPVC) method in Malaysia Construction Industry.

1.4 Scope of Work

The scope of this study is summarized as follow:

- i. The data is collected by distribute survey questionnaire to the project participants who has experience involved in IBS or PPVC project
- ii. The target respondents in this study are the key construction practitioners such as architects, engineers, quantity surveyors, suppliers / manufacturers and contractors in Malaysia.
- iii. This study will focus on the adaptation of using Prefabricated Prefinished Volumetric Construction (PPVC) in Malaysia Construction Industry.
- iv. This study will carry out survey questionnaire on industry experts who had experience in PPVC method.

1.5 Significance of Study

Through this study, the introduction of PPVC method will becoming widely used in future development which leading edge to construction industry. The cost and time performances, planning and measurement and the challenges to sustain in the adoption of Prefabricated Prefinished Volumetric Construction (PPVC) project will be recorded and analyzed. In addition, throughout of this study, PPVC can extensively introduced for many high-rise construction and perhaps can help interested participants find the ways to minimal the problems of constructing affordable and sustainable housing by using PPVC method in the future development of the Malaysia industry. PPVC method also significant helps housing to wide adoption of green material resources, eco-friendly production and the advance engineering equipment on a larger scale in order to enhance the project cost to be more effectiveness.

REFERENCES

- Arashpour et al. (2015) “Optimization of process integration and multi-skilled resource utilization in off-site construction”. *Automation in Construction*, 50, 72–80
- Arashpour et al. (2016) “Analysis of interacting uncertainties in on-site and off-site activities: Implications for hybrid construction”. *International Journal of Project Management*, 34, 1393–1402.
- Arashpour et al. (2016) “Off-site construction optimization: sequencing multiple job classes with time constraints. *Automat. Constr.* 71 (Part 2), 262-270.
- Arashpour et al. (2017) “Optimizing decisions in advanced manufacturing of prefabricated products: Theorizing supply chain configurations in off-site construction”. *Automation in Construction*, 84, 146–153
- Arashpour et al. (2017) “Optimal Process Integration Architectures in Off-site Construction: Theorizing the Use of Multi-skilled Resources. *Architectural Engineering and Design Management*, pp. 1-14.
- Bank Negara Malaysia (2016). ‘Demystifying the Affordable Housing Issue in Malaysia,’ Box article in Annual Report. Kuala Lumpur.
- BCA, B. C. A. (2014) “Code of Practice on Constructability. Requirement for Prefabricated Prefinished Volumetric Construction (PPVC)”. Building and Construction Authority, Singapore.
- BCA, S., (2015) Amendments to Building Control (Buildability and Productivity) Regulations to Further Raise Productivity in the Built Environment Sector.
- BCA, S. (2017b) “Prefabricated Prefinished Volumetric Construction. Building and Construction Authority, Singapore, Prefabricated Prefinished Volumetric Construction (PPVC) Guidebook, Design for Manufacturing and Assembly (DfMA)

- Bon-Gang Hwang et al., (2018) “Key constraints and mitigation strategies for prefabricated prefinished volumetric construction”, *Journal of Cleaner Production*, 183, 183–193.
- Bon-Gang Hwang et al., (2018) “Knowledge-based decision support system for prefabricated prefinished volumetric construction”, *Automation in Construction*, 94 168–178.
- Cao, X.; Li, Z.; Liu, S. (2015) “Study on factors that inhibit the promotion of SI housing system in China”. *Energy Build*, 88, 384–394.c
- Construction Industry Transformation Programme (CITP) 2016-2020, “Driving Construction Excellence Together”, CIMB, Malaysia.
- Cheah Su Ling, Stefanie Joan Almeida, Ho Su Wei (2017) *Affordable Housing: Challenges and the Way Forward*, BNM Quarterly Bulletin.
- Chiang, Y.-H., Chan, E.H.-W., Lok, L.K. (2006) “Prefabrication and barriers to entry- a case study of public housing and institutional buildings in Hong Kong”. *Habitat Int.* 30, 482-499.
- Chong et al. (2017) “A mixed review of the adoption of Building Information Modelling (BIM) for sustainability”. *Journal of Cleaner Production*, 142, 4114-4126.
- C.Z. Li et al. (2017) “Integrating RFID and BIM technologies for mitigating risks and improving schedule performance of prefabricated house construction”. *Journal of Cleaner Production*, 165, 1048-1062.
- C.Z. Li et al. (2018) “A model for simulating schedule risks in prefabrication housing production: A case study of six-day cycle assembly activities in Hong Kong”. *Journal of Cleaner Production*, 185, 366-381.
- Elena M. Generalova, Viktor P. Generalov, Anna A. Kuznetsova, (2016) “Modular buildings in modern construction”, XXV Polish – Russian – Slovak Seminar “Theoretical Foundation of Civil Engineering”.

- Goh and Loosemore (2017) “The impacts of industrialization on construction subcontractors: a resource based view”. *Construction Management and Economics*, 35:5, 288-304.
- Hanna, A.S., Mikhail, G., Iskandar, K.A. (2017) “State of prefab practice in the electrical construction industry: qualitative assessment”. *J. Constr. Eng. Manag.* 143.
- Jaillon, L., Poon, C.S., (2008) “Sustainable construction aspects of using prefabrication in dense urban environment: a Hong Kong case study”. *Construct. Manag. Econ.* 26 (9), 953-966.
- Jaillon et al. (2009) “Quantifying the waste reduction potential of using prefabrication in building construction in Hong Kong”. *Waste Management*, 29, 309–320 311
- Jaillon, L., Poon, C.S., (2010) “Design issues of using prefabrication in Hong Kong building construction”. *Construct. Manag. Econ.* 28 (10), 1025-1042.
- Kamali, M., Hewage, K., (2016) “Life cycle performance of modular buildings: a critical review”. *Renew. Sustain. Energy Rev.* 62, 1171-1183.
- Kamali, M., Hewage, K., (2017) “Development of performance criteria for sustainability evaluation of modular versus conventional construction methods”. *Journal of Cleaner Production*, 142 (Part 4), 3592-3606.
- Khalili, A., Chua, D.K.H., (2013) “IFC-based framework to move beyond individual building elements toward configuring a higher level of prefabrication. *J. Comput. Civ. Eng.* 27, 243-253.
- Kim, Y.W., Azari-N, R., Yi, J.S., Bae, J., (2013) “Environmental impacts comparison between on-site vs. prefabricated Just-In-Time (prefab-JIT) rebar supply in construction projects”. *J. Civ. Eng. Manag.* 19, 647-655.
- Kim, M.-K., Wang, Q., Park, J.-W., Cheng, J.C.P., Sohn, H., Chang, C.-C., (2016) “Automated dimensional quality assurance of full-scale precast concrete elements using laser scanning and BIM”. *Automat. Constr.* 72 (Part 2), 102-114.

- Lei Jiang et.al, (2018) “Constraints on the Promotion of Prefabricated Construction in China”, *Sustainability*, 10, 2516.
- Li et.al, (2011) “Rethinking pre-fabricated construction management using the VP-based IKEA model in Hong Kong”. *Constr. Manag. Econ.*, 29, 233–245.
- Li et.al, (2013) “Exploration of modular build of architectural space”. *Appl Mech Mater*; 357:338-44
- Li et.al, (2013) “Risk identification and assessment of modular construction utilizing fuzzy analytic hierarchy process” (AHP) and simulation.
- Li, C.Z., Hong, J., Xue, F., Shen, G.Q., Xu, X., Luo, L., (2016a) “SWOT analysis and Internet of Things-enabled platform for prefabricated house construction in Hong Kong”. *Habitat Int.* 57, 74-87.
- Li, C.Z., Hong, J., Xue, F., Shen, G.Q., Xu, X., Mok, M.K., (2016b) “Schedule risks in prefabricated house construction in Hong Kong: a social network analysis”. *J. Clean. Prod.* 134 (Part B), 482-494.
- Li et al. (2017) “Schedule risk modeling in prefabrication housing production”. *Journal of Cleaner Production*, 153, 692-706.
- Liew et al. (2018) “Steel Concrete Composite Systems for Modular Construction of High-rise Buildings, 12th International Conference on Advances in Steel-Concrete Composite Structures (ASCCS 2018)
- Luo et al. (2015) "Risk factors affecting practitioners' attitudes toward the implementation of an industrialized building system", *Engineering, Construction and Architectural Management*, Vol. 22 Iss 6 pp. 622 – 643.
- Mao et al. (2015) “Major barriers to off-site construction: the developers’ perspective in China”. *J. Manag. Eng.*, 31 (3), 04014043.
- Mohammad Fadhil Mohammad et.al, (2015) “The Potential Application of IBS Modular System in the Construction of Housing Scheme in Malaysia”, *ASEAN-Turkey ASLI Conferences on Quality of Life 2015AcE-Bs ver. 2: AicQoL2015Jakarta*.

- Muhamad Faiz Musa et al. (2016) “Towards the adoption of modular construction and prefabrication in the construction environment: a case study in Malaysia”. ARPN Journal of Engineering and Applied Sciences, ISSN 1819-6608.
- Mohammad Kamali, Kasun Hewage (2017) “Development of performance criteria for sustainability evaluation of modular versus conventional construction methods”, Journal of Cleaner Production, 142, 3592–3606.
- Ong Ying Rui, Khairulzan Yahya, (2016) “The Productivity Rate of Prefabricated Pre-Finished Volumetric Construction (PPVC)”, Faculty of Civil Engineering, Universiti Teknologi Malaysia.
- Polat, (2008) “Factor affecting the use of precast concrete system in the United States”. J. Construct. Eng. Manag. 134, 169-178.
- Rahman, M.M., (2013) “Barriers of implementing modern methods of construction”. J. Manag. Eng. 30, 69-77.
- Ramaji, I.J., Memari, A.M., (2016) “Product architecture model for multistory modular buildings”. J. Constr. Eng. Manag. 142, 04016047.
- R. Jiang et al. (2018) “A SWOT analysis for promoting off-site construction under the backdrop of China’s new urbanisation”. Journal of Cleaner Production, 173, 225-234.
- Said (2015) “Prefabrication Best Practices and Improvement Opportunities for Electrical Construction”. Journal of Construction Engineering and Management, 04015045-14
- Said, H., (2016) “Modeling and likelihood prediction of prefabrication feasibility for electrical construction firms”. J. Constr. Eng. Manag. 142.
- Tam et al, (2007) “Towards adoption of prefabrication in construction”. Build. Environ. 42 (10), 3642-3654.
- Tam et al, (2015) “Best practice of prefabrication implementation in the Hong Kong public and private sectors”. Journal of Cleaner Production, 109, 216-231.

- Tarek Salama et.al, (2017) “Near optimum selection of module configuration for efficient modular construction”, *Automation in Construction*, 83, 316–329.
- Wang, T., Li, Y., Zhang, L., Li, G., (2016) “Case study of integrated prefab accommodations system for migrant on-site construction workers in China”. *J. Prof. Issues Eng. Educ. Pract.* 142.
- W. Lu et al. (2018) “Searching for an optimal level of prefabrication in construction: An analytical framework”. *Journal of Cleaner Production*, 201, 236-245 237.
- W. Zhang et al, (2018) “The hindrance to using prefabrication in Hong Kong's building industry”. *Journal of Cleaner Production*, 204, 70-81.
- X. Gan et al., (2018) “Barriers to the transition towards off-site construction in China: An Interpretive structural modeling approach”. *Journal of Cleaner Production*, 197, 8-18.
- X. Gan et al. (2018) “Overcoming barriers to off-site construction through engaging stakeholders: A two-mode social network analysis” *Journal of Cleaner Production*, 201, 735-747.
- Zhai et al, (2014) “Factors impeding the offsite production of housing construction in China: an investigation of current practice”. *Construct. Manag. Econ.* Vol 32 (1), 40-52.
- Zhang et al, (2014) “Exploring the challenges to industrialized residential building in China”. *Habitat Int.* 41 (41), 176-184.
- Zhao, X., (2017) “A scientometric review of global BIM research: analysis and visualization”. *Automat. Constr.* 80, 37-47.
- Zhao, X., Feng, Y., Pienaar, J., O'Brien, D., (2017) “Modelling paths of risks associated with BIM implementation in architectural, engineering and construction projects”. *Archit. Sci. Rev.* 60, 472-482.